



Simple Action For the Environment (SAFE)

Registered under: Niraporth Bangladesh Songstha (Safe Bangladesh Organisation, SBO),
Sundarban Village, PO: Ramdubihat, Upuzila: Sadar Dinajpur.



Housing and Hazards

www.housingandhazards.org

Case study: construction of rammed earth house

13 June 2011

Introduction

This case study documents the construction of a rural house, using rammed earth construction technique, which took place during June 2011. It has been undertaken with support from the Australian High Commission, British Women's Association and Housing and Hazards. It details our participatory approach and provides technical information about our techniques and the associated costs.

SAFE is a small NGO working in the Dinajpur district of Bangladesh to:

Reduce the vulnerability of low income households to environmental hazards such as flooding and strong winds.

We do this through promoting improved and appropriate house building techniques – using cheap, locally available materials, and environmental initiatives such as tree planting. With stronger houses that last longer, households in the long run save time and money and are less vulnerable to environmental hazards.

We aim to increase community self reliance by creating skilled and informed local builders, craftsmen and house owners. We do this through a programme of workshops, construction of demonstration houses and material subsidies.



Northern Bangladesh

Participatory Approach

We recognise the importance of participation if our new techniques are going to be accepted and spread within the local population. This house has been built through a partnership between SAFE and the household. Both parties contributed labour and materials in an approximately 50/50 split. This split was agreed at the outset and a simple hand written contract outlining each party's responsibilities was signed.

The size and type of house was decided by the household based on available materials and space requirements.

The house included some new techniques and we made sure that the household and builders understood these fully. As part of this we organised a 1-day building-for-safety workshop for households in the local area, students and local builders. These workshops included practical demonstration of these new techniques.

Improved Construction Techniques


The house has been built with the household of Udoi and Doiya Rani Roy in Baniar Para, Sundarban village, Dinajpur. The house was built to replace an existing sleeping room which was in poor condition. The house comprises of one room of outside dimensions 17.5ft by 8.5ft. The house is built on brick foundations. The structure is made rammed earth with bamboo reinforcement. The roof is of hipped (*cho-chala*) construction and made with bamboo frame and corrugated iron (CI) sheet. SAFE has used added several low cost improvements to this traditional house and these are as follows:

Refer to construction drawings in Appendix A.

Foundation

A layer of plastic sheet has been used to provide a damp proof layer between the top of the brick foundation and the mud walls.

Walls



Map of Sundarban Union showing location of demonstration house



Vertical and horizontal bamboo reinforcement used.

Walls are made using rammed earth with cement stabilised mud, a technique which makes the wall much stronger and more resistant to water. The mud was mixed with 5% cement^{1,2} (refer to footnotes for more information on this technique). Cement stabilised earth was used only for the bottom 6ft (bottom two layers) of the wall – above this, protection from rain is given by the roof overhang.

The forms were constructed on site of dimensions 6'8" x 3' with made using 1.5" thk timber boards. See pictures.

An overhanging layer of bricks has been built into the wall approximately half way up. Any water which comes into contact with the wall above these bricks will drip clear of the lower section of the wall – reducing damage.

Ventilation – 3 windows and ventilation holes have been used to provide adequate ventilation within the house.

A bamboo ring beam has been constructed at the top of the walls fixed to the vertical reinforcement.

Roof


The roof is secured to the walls using the bamboo vertical reinforcement. Overhang of approx 2" is given to give adequate protection from rain. Nylon rope has been used over jute rope for its longevity.

Costs

A cost comparison has been carried out between the rammed earth and brick walled house. It is assumed that the foundations and roof, and other costs such as the door and window

¹ Iftekar, K.A. Handbook on Design and Construction of Housing for Flood-Prone Rural Areas of Bangladesh, ADPC 2005. Available at www.sheltercentre.org

² Norton, J. Building with Earth, A Handbook, Practical Action, 1997



Formwork fixing detail (taken from Building with Earth, a handbook – see footnote 1)



Damp-proof course between brick foundation and earth wall

frames to be of similar construction and so have been discounted. It is also assumed that the household can provide 3-4 labourers during construction at no cost, however skilled labour for the setting of the rammed earth formwork will be required and is included.

Refer to the cost comparison in Appendix B. The total cost of the rammed earth walls comes Tk12,769 or 28Tk per sqft. The brick wall cost comes to 51Tk/sqft – approx 55% of the cost of using brick wall construction.

For more information contact:

Azit Roy, T: +880 (0)1726 007 343, E: azit_sorkar@yahoo.com

John Arnold, T: +880 (0)1753 858 660 E: johnarnold700@yahoo.co.uk

In the UK:

Robert Hodgson (Housing and Hazards), T: +44 (0)1884 821239

R.L.P.Hodgson@exeter.ac.uk



Floor structure for loft storage + bamboo ring beam




Arched windows formed using bricks



Single layer of protruding bricks provide extra protection to erosion from rain water.





Appendix A – construction drawings






boundary wall
BOUNDARY WALL

A


VERTICAL BAMBOO REINFORCEMENT ADJACENT TO ALL OPENING & CORNERS.

WALL PLATE FIXED TO VERTICAL REINFORCEMENT WITH NYLON ROPE OR CFI WIRE.



BAMBOO SOCKETS SET IN WALL TO TAKE HORIZONTAL TIE FOR ADJOINING BOUNDARY WALL

DETAIL B



BLOCKS
TIMBER SET IN WALL TO FIX DOOR/WINDOW FRAME FOR ALL WINDOWS

A

boundary wall


Verandah

COW SHED

PLAN AT WINDOW LVL.

PAGE 2/3

DETAIL A



RAFTER, 2"x2" @ 2 1/2' c/c


2x1 PURLINS @ 2'8" c/c MIN.

C.I SHEET (MIN. 0.35mm GAUGE)

TIES, 2"x2", 3 No. EVENLY SPACED; OR TO SUIT STORAGE REQUIREMENT

BAMBOO, CEMENTED IN PLACE AFTER WALL CONSTRUCTION TO SUPPORT VERANDAH.

BAMBOO WALL PLATE (RING BEAM); SECURED TO VERTICAL REINFORCEMENT & FIXED AT CORNERS.




SECTION A-A

SEE DETAIL 'B'

APPROX. GROUND LVL.

SAND LAYER ON FORMATION OF FIRM SILTY SAND

DETAIL B
(SCALE 1" : 2mm)



Appendix B – Cost comparison of cement stabilised rammed earth against brick wall




Budget cost for standard brick/cement wall

Assumptions	
Foundations are assumed to be same as mud block wall and are not included	
RC lintel is added for stability	
Plaster for one side is included	
Lowest quality bricks used	

Brick size			
Standard brick size = 25 x 7.5 x 12cms			
incl mortar joint = 26 x 8.5 x 13cms			
Convert			
25	9.8 in	26	10.2 in
7.5	3.0 in	8.5	3.3 in
12	4.7 in	13	5.1 in
Volume of 1 brick without mortar course		0.079 cuft	
Volume of 1 brick with mortar course		0.10 cuft	

Cement	
Cost of cement - 50kg bag	360 Tk
Convert to volume @1500 kg/m ³	0.033223 m ³
convert to cuft @1m ³ = 35.32cuft	1.172757 cuft per 50kg bag

Labour	
Skilled eg. mason	200 Tk/day
Labourer	120 Tk/day



Size of Wall	
Plan area	10.63 sqft
Volume of wall	95.63 cuft

Calculate no. bricks	
Brick volume incl. mortar joint from above	0.10 cuft
Total bricks	942 no.
Cost of bricks @ Tk5/brick	4712 Tk

Mortar	
Sand - 1 trailer at Tk400/ load	100 Tk

<i>Use rule of thumb 0.3m³ mortar per 1000 bricks</i>	
Volume of mortar	0.28 m ³
Convert to cuft @ 1m ³ = 35.32cuft	10.0 cuft
Volume of cement @ 1:4	2.0 cuft
No. bags cement	1.7 no.
Cost of cement (using rate above)	613 Tk

Labour - laying bricks	
say 3 days for mason (Tk200/day) and labourer (Tk120/d)	960 Tk

Plaster	
Cement - say 1.5 bags @ 360/bag	540 Tk
Sand (use load from before)	100 Tk
Labour - say 1 mason, 1 labourer for 2 days	690 Tk

Lintel	
M/S Reinforcement, 8kg @ Tk44/kg	352 Tk
Tying wire	70 Tk
Cement - say 1 bag @Tk360/bag	360 Tk
Brick chips (80 no. bricks @ Tk4/brick)	320 Tk
Sand	100 Tk
Labour - say 1 mason, 1 labourer for 1 day	320 Tk

Total cost	8278 Tk
-------------------	----------------

Total wall length	18 ft
Wall height	9 ft
Area	162 sqft
Cost per sqft.	51 Tk/sqft

Cost of Rammed Earth Technique

Unstabilised mud

Assumptions	
Assume house size of 8.5ft x 17.5ft with 9ft high walls	
Shuttering cost not included	
Scaffolding cost not included	
Assume construction in 3' layers	
Assume that in 3 days, 2 men will construct 1 layer	
Use 1 skilled labour and 1 labourer	
Household is required to prepare and carry earth and assist with ramming - 2/3 people for duration of construction	
Earth is assumed to be available locally with no transport costs.	
Any minor repair/finishing to be done by household	

Labour	
Skilled	200 Tk/day
Labourer	120 Tk/day
Total daily cost of labour	320 Tk
No. of layers	3 no.
No. of days for construction*	11 days
*Assume 2 extra days as work slows on top layer and to construct windows.	
Total labour cost	3520 Tk
Bamboo for reinforcement	1500 Tk
Cost of consumerables eg. rope for shutters	500 Tk
Total cost	5520 Tk

Unit cost	
Total length of wall	50 ft
Height of wall	9 ft
Area of wall	450 sqft
Cost per ft of wall	12 Tk/ft

Extra cost of cement stabilisation

Assumptions	
Only bottom 2 layers are stabilised as top layer will be protected by roof overhang	
Wall is 10" thick	
1-2 extra labourers required during construction - assume 1 is paid @120Tk/day and one is provided by household	

Cement cost	
volume of walls =	250 cuft.
assume compaction of	1.5
volume of earth	375 cuft.
volume of cement @ 5%	18.75 cuft.
volume of 50kg bag cement	1.17 cuft/bag
total cement required	16 bags
Cost per bag	370 Tk
Total cost of cement	5929 Tk

Extra labour	
No. days of construction	11 days
Labour cost	1320 Tk
Total cost	7249 Tk

Unit cost	
Total length of wall	50 ft
Height of wall	9 ft
Area of wall	450 sqft
Cost per ft of wall	16 Tk/ft

Total cost - rammed earth + stabilisation		12769 Tk
Unit Cost		
Total length of wall	50 ft	
Height of wall	9 ft	
Area of wall	450 sqft	
Cost per ft of wall	28 Tk/sqft	